
Recycling enlargement & Tree Pad construction attached

2 messages

David Carimi <david@carimiconstruction.com>
To: Sidney Torres <Storres@sdtivcapital.com>

Tue, Sep 14, 2021 at 12:08 PM

Sidney
See attached and give me a call. I need to meet with the city of Kenner if we want to move forward with this.

Thanks



530 S. Jefferson Davis Pkwy - Suite 101, New Orleans, LA 70119
ph: (504) 524-5990 • fx: (504) 524-5991

 **Kenner Yard.pdf**
611K

Sidney Torres <storres@sdtivcapital.com>
To: David Carimi <david@carimiconstruction.com>


Tue, Sep 14, 2021 at 4:37 PM

I will review tonight

Sidney D. Torres, IV
IV Capital, LLC
<https://ivwaste.com/>
www.sdtivcapital.com
www.thecoveeleuthera.com
Facebook | Instagram

On Sep 14, 2021, at 12:08 PM, David Carimi <david@carimiconstruction.com> wrote:

[Quoted text hidden]
<Kenner Yard.pdf>



Date: 9/14/21

ISSUED TO:
Sidney Torres

CO # 791M

Job:
730 S. Pierce St.

Carimi Construction & Development, LLC
530 S Jefferson Davis Pkwy
New Orleans, LA 70119
504-524-5990
504-524-5991 fax

Scope of Work:
Kenner: Recycling Pad/Enclosure Enlarged.

General Conditions - 5107

Project Management	\$1,468
Site Manager	\$730
General Conditions - 5107 Total	\$2,198

Concrete - 5553: Recycling Pad/Enclosure Enlarged.

Demo existing chain wall, haul off site	
Form new chain wall 105 lineal feet 30" tall 11" wide with #4 rebar and schedule 40 fence poles on 6'0/c	
Labor and Materials	\$11,775
Add 23' 6" x 58' to existing slab 6 inches thick with highway mesh, sloped towards existing drain	
Labor and Materials	\$16,131
Concrete - 5553 Total	\$27,906

Landscape - 5112: Recycling Pad/Enclosure Enlarged.

Lime stone to dress up surrounding areas.	\$1,200
Carriage bolts, fasteners, washers, layout supplies, and nuts to install wood fence	\$798
Drill bits to drill through metal post to attach wood fence	\$175
Fasteners to install wood fence on concrete knee wall.	\$202
Landscape - 5112 Total	\$2,375

Equipment Rental - 5137

6500 Watt Generator rental (Sunbelt) 1 day, pickup, and delivery charge to run circular saws and power tools to install formwork for slab pour	\$455
Two light towers for concrete pour	\$668

Trash pump rental to pump water out for concrete pour \$154
Equipment Rental - 5137 Total \$1,277

Framing Material - 5579: Recycling Pad/Enclosure Enlarged.
Treated pine material to install 9' tall wall at concrete knee walls. (60) 2x12x12. \$1,320
Labor \$4,050
Framing Material - 5579 \$5,370

Subtotal: **\$39,126**

P/O: \$5,869

Total Due: \$44,994

X _____
Name

Date